

BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Providing Gym equipments at Naraseepura Park in Ward No.9

Agency:-M/s KRIDL

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of M/s KRIDL		
			Unit	Rate in Figures	Rate in Words
1	92.21	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	Cum	263.94	Rupees Two Hundred Sixty Three And Paise Ninety Four Only
2	205.00	Providing and fixing precast solid concrete kerb stones made out of No.272.21 CC. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc.,	Nos	432.48	Rupees Four Hundred Thirty Two And Paise Forty Eight Only
3	36.80	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour	Sqm	39.22	Rupees Thirty Nine And Paise Twenty Two Only
4	36.80	Providing and applying spray painting in two coat (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	90.10	Rupees Ninety And Paise Ten Only
5	39.53	Providing and laying in position plain cement concrete of Mix CC 1:4:8 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour HOM of machinery curing complete as per specification.	Cum	5408.12	Rupees Five Thousand Four Hundred Eight And Paise Twelve Only
6	31.58	Providing and laying in position plain cement concrete of Mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.549 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour HOM of machinery curing complete as per specification	Cum	5599.98	Rupees Five Thousand Five Hundred Ninety Nine And Paise Ninety Eight Only
7	257.25	Providing and fixing cement base precast, pre-polished cement concrete designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, including cutting, gridding the edge to half/full round wherever required, labour curing complete as per specification.	Sqm	1305.92	Rupees One Thousand Three Hundred Five And Paise Ninety Two Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

App Qty	Description of work	Approved Rates of M/s KRIDL		
		Unit	Rate in Figures	Rate in Words
8	2.00 Supply and fixing of Seated Chest Press. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO NobelGreat Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO 7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules.	Nos	230000.00	Rupees Two Lakh(s) Thirty Thousand Only
9	2.00 Supply and fixing of HD Health Walker. Metal. All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded Joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules.	Nos	140000.00	Rupees One Lakh(s) Forty Thousand Only
10	2.00 Supply and fixing of HD Waist Twister Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of .80-120 microns, All metal parts are tested in our salt spray machine that uses a 5% NaCl, solution: in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules	Nos	130000.00	Rupees One Lakh(s) Thirty Thousand Only
11	2.00 Supply and fixing of Twist Stepper. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules.	Nos	180000.00	Rupees One Lakh(s) Eighty Thousand Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Division
Yelahanka Zone

App Qty	Description of work	Approved Rates of M/s KRIDL		
		Unit	Rate in Figures	Rate in Words
12	2.00	Nos	115000.00	Rupees One Lakh(s) Fifteen Thousand Only
13	2.00	Nos	165000.00	Rupees One Lakh(s) Sixty Five Thousand Only
14	2.00	Nos	125000.00	Rupees One Lakh(s) Twenty Five Thousand Only
15	2.00	Nos	170000.00	Rupees One Lakh(s) Seventy Thousand Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka

App Qty	Description of work	Approved Rates of M/s KRIDL		
		Unit	Rate in Figures	Rate in Words
16	1.00	Nos	160000.00	Rupees One Lakh(s) Sixty Thousand Only
17	1.00	Nos	140000.00	Rupees One Lakh(s) Forty Thousand Only
18	7.00	Nos	10550.00	Rupees Ten Thousand Five Hundred and Fifty Only
19	92.21	Cum	82.60	Rupees Eighty Two And Paise Sixty Only
20	2.00	Nos	4800.00	Rupees Four Thousand Eight Hundred Only
21			12.00%	Twelve Percent

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92